BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/08/2018-19 Dated: 18-02-2019

APPROVED TENDER SCHEDULE –'B'

Item-05

Name of Work::Providing UGD Work System in ward no:01 of Yelahanka Sub Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.RAJESWAREN SATHEESH (SATHYA CONSTRUCTIONS)	
				Rate	Rate in Words
1	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5. (P.No. 5, I.No. 2.4) SR 2018-19	Cum	554.37	326.98	Rupees Three Hundred Twenty Six and Paise Ninety Eight Only
2	KSRB 12-5.1 :Constructing brick masonry circular type manhole 0.91 m internal dia at bottom 0.91m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement foundation concrete M10 mix using 40mm and downsize granite metal and making necessary channel in cement concrete M50 mix with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty , HD-20 grade designation) 560mm internal diameter confirming IS:12592, total weight cover and frame to be not less than 182kg fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complete as per specifications.(Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid separately) Specification No. KBS 12.4 Page No. 72/ Item No. 11.37 PWD SR 2018-19a) Deep 0.91 mtr	Nos	3.00	16990.16	Rupees Sixteen Thousand Nine Hundred Ninety and Paise Sixteen Only
	B) Deep 1.67 mtr		4.00	28057.73	Rupees Twenty Eight Thousand Fifty Seven and Paise Seventy Three Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.RAJESWAREN SATHEESH (SATHYA CONSTRUCTIONS)	
				Rate	Rate in Words
3	KSRB 12-5.3 : Constructing brick masonry circular type manhole 1.22 m internal dia at bottom 1.68m deep and 0.56m dia at top with table moulded non-modular bricks of class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement foundation concrete M10 mix using 40mm and downsize granite metal and making necessary channel in cement concrete M15 mix with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty , HD-20 grade designation) 560mm internal diameter confirming IS:12592, total weight cover and frame to be not less than 182kg fixed in cement concrete M15 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complete as per specifications.(Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid separately) Specification No. KBS 12.4 Page No. 73/ Item No. 11.39 Item No. 11.39 PWD SR 2018-19 Deep 1.68 mtr	Nos	2.00	33874.02	Rupees Thirty Three Thousand Eight Hundred Seventy Four and Paise Two Only
	B) Deep 2.29 mtr	Nos	2.00	40269.16	Rupees Forty Thousand Two Hundred Sixty Nine and Paise Sixteen Only
4	KSRB 12-1.1 : Providing and laying in position to required level or slope 200mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications.Specification No. KBS 12.2.5/12.7 Page No. 72/ Item No. 11.3/ PWD SR201819	Mtr	310.00	562.68	Rupees Five Hundred Sixty Two and Paise Sixty Eight Only
5	KSRB 12-6.1 : Providing 20mm square M.S footrest and fixing in manhole with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 12.4.6.(P.No.73, I.No.11.44) SR 2018-19)	Nos	40.00	318.89	Rupees Three Hundred Eighteen and Paise Eighty Nine Only
6	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. (P.No. 6, I.No. 2.11) SR 2018-19	Cum	554.37	87.81	Rupees Eighty Seven and Paise Eighty One Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.